

TMT MANITOU CHAIN SYSTEM CHECK LIST

MOUNTING

- 1) **Lever 2** 9 o'clock Side shift boom fully left.
 - 2) **Lever 1** 3 o'clock Extend Boom as required.
 - 3) **Lever 2** 6 o'clock Lock Forks in place.
 - 4) **Lever 1** 12 o'clock Raise Forklift as required.
 - 5) **Lever 1** 9 o'clock Retract the Boom as required.
 - 6) Attach the Chains.
 - 7) **Lever 2** 12 o'clock Tilt Forklift fully backward.
 - 8) Connect Trailer Lights.
-

DISMOUNTING

- 1) Disconnect the electrical cable.
- 2) **Lever 2** 6 o'clock Tilt Forklift fully forward.
- 3) Disconnect and remove the chains.
- 4) Alternate levers until tires touch the ground:
 - Lever 1** 3 o'clock Extend Boom as required.
 - Lever 1** 6 o'clock Lower the Forklift as required.
- 7) **Lever 2** 12 o'clock Tilt the Forklift back.
- 8) Back out of fork sleeves.